

مولانا آزاد نیشنل اردو یونیورسٹی

मौलाना आजाद नेशनल उर्दू यूनिवर्सिटी

MAULANA AZAD NATIONAL URDU UNIVERSITY

A Central University established by an Act of Parliament in 1998

(Accredited "A" Grade by NAAC)



No. MANUU/CD/F.317/2018-19/399

Dated: 19/12/2018

Notice Inviting Quotation

NIQ No. 37/MANUU/CD/2018-19/

Sealed item rate quotations are invited for Preparation of Volleyball and Badminton Court in Gulzar Girls Hostel at MANUU Campus to reach the office of the Executive Engineer, Engineering Section, MANUU Gachibowli, Hyderabad up to 3.00 pm on or before 28/12/2018. The quotation will be opened on the same day at 3.30 pm in the presence of intending bidders. Blank quotation form can be obtain from the above office during office hours in all working days and upto 2.00 pm on 28/12/2018.

Name of the Work: *Preparation of Volleyball and Badminton Court in Gulzar Girls Hostel at MANUU Campus, Hyderabad.*


S.No.	Description of item	Qty	Unit	Rate		Amount
				In fig	In words	
As per attached Schedule of Quantities						

Term and conditions:

1. The work shall be executed as per CPWD specification Vol-I &II as per manufacturer's specifications.
2. Time allowed is 15 days.
3. The payment shall be as per actual execution and measurement at site.
4. The rates quoted are net and nothing extra shall be paid on account of taxes, octoria etc.
5. The Income tax and GST shall be deducted as per applicable and notified by Govt.of India.

CONTRACTOR

Address


19/12/2018
Executive Engineer

Copy to

1. The Office of the Registrar
2. Director CIT for uploading in the University website
3. Notice Board

Schedule of Quantities

Name of the Work: *Preparation of Volleyball and Badminton Court in Gulzar Girls Hostel at MANUU Campus, Hyderabad.*

S.No.	Description of items	Quantity	Units	Rate		Amount
				in Fig	In Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.					
1.1	All kinds of soil	15	cum			
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing :	3.15	cum			
2.1	1:5:10 (1 cement : 5 coarse sand (zone-III) : 10 graded stone aggregate 40 mm nominal size).					
3	Brick work with non modular fly ash bricks conforming to IS:12894, class designation 10 average compressive strength in super structure above plinth level up to floor V level in :					
3.1	Cement mortar 1:6 (1 cement: 6 Coarse sand)	10	cum			
4	12 mm cement plaster finished with a floating coat of neat cement of mix					
4.1	1:4 (1 cement: 4 fine sand)	210	Sqm			

5	Hiring the JCB for leveling the ground	10	hours			
6	Supplying and filling morram at site	100	cum			
	Total					-

Terms and conditions:

- 1 The work shall be executed as per CPWD specification Vol-I & II as per manufacturer's specifications.
- 2 Time allowed is 15 days.
- 3 The payment shall be as per actual execution and measurement at site.
- 4 The rates quoted are net and nothing extra shall be paid on account
- 5 The income tax shall be deducted as per applicable.

Contractor

Address



Executive Engineer

MANUU