

مولانا آزاد نیشنل اردو یونیورسٹی
مولانا آزاد نیشنل اردو یونیورسٹی

MAULANA AZAD NATIONAL URDU UNIVERSITY
(A Central University)



No. MANUU/CD/F.133/2019-20/

Dated: 29/04/2019

NIO No. 83 /MANUU/ES/F.133/2019-20/ dated: 29/04/2019

The Executive Engineer, MANUU Hyderabad invites on behalf of Vice-Chancellor, Sealed item rate quotations from CPWD contractors/reputed service agencies for the following work so as to reach this office upto 15:00 PM on 03/05/2019. The quotation will be opened on the same day at 15:30 PM. Blank quotation form can be obtain from this office during office hours in all working days and upto 14:00 PM on 03/05/2019.

Name of the Work: *Repainting and Repair works in PVC Residence at MANUU Campus Hyderabad.*

S.No.	Description of item	Qty	Unit	Rate		Amount
				In fig	In words	
As per attached Schedule of Quantities						

Term and conditions:

1. The work shall be carried out as per CPWD Specifications 2009 Vol-I & II with up to date correction
2. The work should be completed within three (3) days from the date of Issue of Work Order.
3. The rates should be quoted in figures and words and inclusive of all taxes, duties and nothing will be paid extra.
4. The contractor has to make his own arrangements for water & power etc., which is required for the completion of work.
5. Necessary recoveries as applicable will be deducted from the bill.
6. The payment will be made after satisfactory completion of work and as per actual measurements recorded.

CONTRACTOR
Address


Executive Engineer

Copy to

1. The Office of the Registrar
2. Director CIT for uploading in the University website
3. Notice Board

Name of Work: Repainting and Repair works in PVC Residence at MANUU, Hyderabad.
Schedule of Quantities


No.	Description Of Item	Unit	Qty	Rate In Fig & Words	Amount
1	French spirit polishing :				
1.1	Two or more coats on new works including a coat of wood filler	Sqm	90		
2	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour.				
2.1	One coat	Sqm	650		
3	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.				
3.1	Granite of any colour and shade				
1.1	Area of slab upto 0.50 sqm	Sqm	5		
4	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	Sqm	5		

No.	Description Of Item	Unit	Qty	Rate In Fig & Words	Amount
5	Providing and laying Vitrified tiles in floor with different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately).				
1	Size of Tile 600x600 mm	Sqm	10		
5	Providing and fixing in wall lining flat pressed three layer (medium density) particle board or graded wood Pre-laminated one side decorative lamination and other side balancing lamination Grade I, Type II, IS : 12823 marked, including priming coat on unexposed surface, with necessary fixing arrangement and screws etc. complete :				
1	18 mm Thick	Sqm	2		
7	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.				
1	For thickness of tiles 10 mm to 25 mm	Sqm	10		
	Total				

Terms and Conditions:

1. The work shall be carried out as per CPWD Specifications 2009 Volume-I & II with up to date correction slips and as per the
2. The work should be completed within three (3) days from the date of Issue of the Work Order.
3. The rates should be quoted in figures and words and inclusive of all taxes, duties and nothing will be paid extra.
4. The contractor has to make his own arrangements for water and power etc., which is required for the completion of the work.
5. Necessary recoveries as applicable will be deducted from the bill.
6. The payment will be made after satisfactory of completion of work and as per actual measurements recorded.

Contractor
Seal & Address


26/4/19
Executive Engineer
MANUU, Hyderabad