

مولانا آزاد نیشنل اردو یونیورسٹی مولانا آزاد نیشنل اردو یونیورسٹی

MAULANA AZAD NATIONAL URDU UNIVERSITY
(A Central University)



No. MANUU/CD/F.133/2019-20/17

Dated: 02/04/2019

Notice Inviting Quotation

NIQ No.01/MANUU/CD/2019-20/

Name of the Work: *Repairing of Water supply line in front of Sport Ground at MANUU Campus*

Sealed item rate quotations are invited from reputed Agencies who fulfill the eligibility criteria for Repairing of Water supply line in front of Sport Ground at MANUU Campus to reach the office of the Executive Engineer, Engineering Section, MANUU Gachibowli, Hyderabad up to 3.00 pm on or before 08/04/2019. The quotation will be opened on the same day at 3.30 pm in the presence of intending bidders. Blank quotation form can be obtain from the above office during office hours in all working days and upto 2.00 pm on 08/04/2019.

S.No.	Description of item	Qty	Unit	Rate		Amount
				In fig	In words	
As per attached Schedule of Quantities						

Term and conditions:

1. The work shall be executed as per CPWD specification Vol-I & II as per manufacturer's specifications.
2. Time allowed is 7 days.
3. The payment shall be as per actual execution and measurement at site.
4. The rates quoted are net and nothing extra shall be paid on account of taxes, octoria etc.
5. The Income tax and GST shall be deducted as per applicable and notified by Govt.of India.

CONTRACTOR
Address


Executive Engineer

Copy to

1. The Office of the Registrar
2. Director CIT for uploading in the University website
3. Notice Board

Schedule of Quantities

Name of the Work: *Repairing of water supply line in front of Sport Ground at MANUU, Hyderabad.*

S.No.	Description of items	Quantity	Units	Rate		Amount
				in Fig	In Words	
1	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge					
1.1	50 mm nominal outer dia Pipes	12	mtr			
2	Providing and fixing MABT 50 mm	2	Nos.			
3	Providing and fixing FABT 50 mm	2	Nos.			
4	Providing and fixing Ball Wall 50 mm (disconnect the existing GI line and provide the new ball wall)	1	No.			
5	Repair work of arresting leakage including excavation and replacing damaged fittings and refilling earth.					
5.1	Jointing in HDPE Horticulture pipe line for Harita Haram to supply water for the Central lawn	4	Job			
	Total					-

Terms and conditions:

- 1 The work shall be executed as per CPWD specification Vol-I & II as per manufacturer's specifications.
- 2 Time allowed is 07 days.
- 3 The payment shall be as per actual execution and measurement at site.
- 4 The rates quoted are net and nothing extra shall be paid on account of ta
- 5 The income tax shall be deducted as per applicable.

Contractor
Address


Executive Engineer
 MANUU