



## Schedule of Quantities


**Name of the Work:** *Repair of damaged kota flooring at Centralized kitchen at Boys Hostel-II, MANUU Campus, Hyderabad*

S.No.	Description of item	Qty	Units	Rate		Amount
				in fig	in words	
1	<b>KOTA STONE FLOORING</b> Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) :					
1.1	25 mm thick	130	Sqm			
2	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.					
2.1	For thickness of tiles 10 mm to 25 mm	170	Sqm			
3	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	40	Sqm			
<b>Total</b>						

**Term and conditions:**

- 1 The work shall be carried out as per CPWD Specifications 2009 Vol-I & II with up to date correction
- 2 Time allowed is Fifteen(15) days from the date of Issue of Work Order.
- 3 The rates quoted shall be inclusive of all taxes, duties and nothing will be paid extra.
- 4 Necessary recoveries of IT and GST as applicable will be deducted from the bill.
- 5 The payment will be made after satisfactory completion of work and as per actual measurements recorded at site.

**CONTRACTOR**  
Address

  
 Executive Engineer